

Name of work :- Strengthening of 30 mtr. wide master road & special repair of 10 mtr. wide internal roads in Sector-23, U/E, Sonipat. Providing & laying of 25 mm thick premix carpet with seal coat type "B" and all other works contingent thereto".

A/C Rs. 18.65 lacs

CONTRACT SCHEDULE OF RATES

Sr. No.	HSR Item/ Appd. Item	Description	Qty.	Unit	Rate [in Rs.]
1	Appd.item	Providing and laying of 75 mm thick lean bituminous macadam using aggregate size 45 mm to 2.8 mm with bitumen contents 2% of total weight of mix (bitumen grade 80/1000) prepared by latest MOST specification with hot mix plant and laying at site of work for all lead with mechanical paver and rolling with road roller giving density as job mix formula complete in all respect (including cost of bitumen)	60 cum	P. cum	4409.65
2	Appd.item	Supply and laying of tack coat with 50 kg bitumen per 100 sqm (including cost of bitumen of grade 80/100) complete in all respects as desired and directed by the Engineer-In-Charge on existing black top surface.	8085 sqm	P. sqm.	24.00
3	Appd item	Providing and laying of 25 mm thick compacted premixed carpet with stone aggregate 13.2 mm gauge @1.10 cum per 100 qm. approved quality of bitumen grade 80/100 @ 182.50 kg./100 sqm with bitumen contents as per latest PWD/MOST specf. mixed at hot mixed plant and laying with mech. mixer and rolling with road roller giving density of job mix formulas complete in all respect as per specifications to the entire satisfaction of the Engineer-in-charge with "B" type seal coat using coarse sand @ 0.60 cum per 100 sqm and bitumen @ 68 kg /100 sqm of grade 80/100 complete in all respect to the entire satisfaction of Engineer-In-charge (including the cost of bitumen).	8085 sqm	P. sqm	173.75

Exeuctive Engineer,
HUDA Division,
Sonipat.